


9'0" CENTER TO

2' 5" CENTER TO CENTER

	PARTS LIST								
ITEM QTY PART		PART NO.	PART DESCRIPTION	UNIT WT.	NET WT.				
1	4 PC312 3-1/2" FENCE POST CAP				0.59	2.34			
2	4 X-UB1358 1/2" X 3-5/8" X 5-1/2" X 3" U-BOLT (HDG.)				0.66	2.63			
3	2 X-FP24 4 POST SUPPORT BRACKET			35 1/2 in	14.99	29.98			
4	8 G12FW 1/2" HDG USS FLATWASHER		1/2" HDG USS FLATWASHER		0.03	0.27			
5	8	G12LW	1/2" HDG LOCKWASHER		0.01	0.11			
6	8	G12NUT	1/2" HDG HEAVY 2H HEX NUT		0.07	0.57			
7	1	GRS24	24" X 10' GRIP SPAN BRIDGE CHANNEL		67.98	67.98			
8	4	SPLICE	SPLICE FOR GRIP STRUT	7 3/8 in	0.53	2.10			
9	8	G3803	3/8" x 3" HDG HEX BOLT GR5		0.12	0.97			
10	8	G38FW	3/8" HDG USS FLATWASHER		0.01	0.09			
11	8	G38LW	3/8" HDG LOCKWASHER		0.01	0.05			
12	8	G38NUT	3/8" HDG HEAVY 2H HEX NUT		0.03	0.27			
13	4	P3160	3" SCH. 40 PIPE (3.5" O.D. x 0.216" WALL) A500	160 in	101.25	404.99			
					TOTAL MIT #	E11 10			

TOTAL WT. # 511.18



DIRECT BURIAL FOOTING

TOLERANCE NOTES

TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE: SAWED, SHEARED AND GAS CUT EDGES (± 0.030°) DRILLED AND GAS CUT HOLES (± 0.030°) - NO CONING OF HOLES LASER CUT EDGES AND HOLES (± 0.010°) - NO CONING OF HOLES BENDS ARE ± 1/2 DEGREE

ALL OTHER MACHINING (± 0.030") ALL OTHER ASSEMBLY (± 0.060")

PROPRIETARY NOTE:
THE DATA AND TECHNIQUES CONTAINED IN THIS DRAWING ARE PROPRIETARY INFORMATION OF VALMONT
INDUSTRIES AND CONSIDERED A TRADE SECRET. ANY USE OR DISCLOSURE WITHOUT THE CONSENT OF
VALMONT INDUSTRIES IS STRUCTLY PROHIBITED.

DESCRIPTION

FOUR POST GRIP-SPAN BRIDGE KITS WITH NO TRAPEZE WITH 13' 4" DIRECT BURIAL POSTS



Engineering Support Team: 1-888-753-7446

Locations: New York, NY Atlanta, GA Los Angeles, CA Plymouth, IN Salem, OR Dallas, TX

CPD NO.		0.	DRAWN BY	ENG. APPROVAL	PART NO.	Γ.	
			CEK 5/23/2011		4B24D	0	
	CLASS	SUB	DRAWING USAGE	CHECKED BY	DWG. NO.	η :	
	81	02	CUSTOMER	BMC 5/23/2011	4B24D	_	